1095

TUMKUR DISTRICT BOARD OFFICE.

Notification dated 22nd July 1929.

Notice is hereby given that sealed tenders will be received at the Office of the President, District Board, Tumkur, up to 2 P.M., on the 20th August 1929, for constructing a musafirkhana at Honnudike Tumkur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the 15th of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Office of the President, District Board, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on typed forms which may be obtained from the office of the President. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. one hundred (100) only in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for constructing a musafirkhana at Honnudike" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the President, District Board, Tumkur, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the President's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rates should be written legibly both in figures and words without correction.

10. The contractor will not be allowed to claim enhanced rates after the submission of the tender at any stage.

11. The decision of the President, District Board, will be final and legally binding on the contractor in case of disputes about the rates, qualities and quantities of work:—

Abstract of the estimate.

Serial No.	Items of work	Quantity	Per	Rate	Remarks
1	Earthwork excavating foundation and filling in basement.	31	C.yd.	Rs.	
2	Jelly concrete in mortar	172	C.ft.		
3	Burnt stone in clay	992	,,		
4	Burnt brick in clay	1,265	,,		
5	Burnt stone slabs 6" thick including dressing	227	S.ft.		
6	Burnt stone slabs 6" thick with two line dressing and cutting grooves at top.	33	,,		
7	Plastering with chunam	25·08	Sqr.		
8	Chunam pointing	1·73	,,		
9	White washing two coats	25·08	,,		
10	Junglewood wrought and put up 2 feet a part from centre to center with woodoiling	62·40	C.ft.		
11	Teakwood battened doors with iron works, complete.	132	S.ft.		
12	Teakwood battened windows with ¼" iron bars, etc., complete.	72	,,		
13	Teakwood ventilators with glazed shutters and cross bars, etc., complete.	6	,,		
14	Roofing with first class Mangalore tiles with teak reepers, etc., complete.	10·56	Sqr.		
15	Mangalore Ridge tiles set in mortar and cement pointing.	40	R.ft.		
16	Chunam borders 6" thick including plastering	48	,,		
17	Flooring with Cudappah slabs over3 " concrete and cement pointing.	5·33	Sqr.		
18	Wood oiling	2·88	,,		
19	Chocolate painting	1·72	,,		
20	Tarring to wood work	L. S.	12 Rs.		

G. B. HERLIKAR